

# CRANE


*modern kitchen equipment*



# there's nothing finer than a *Crane Preferred* kitchen



## Crane colored fixtures



Crane kitchen sinks are available in white and eight attractive pastel colors which permit a wide variety of decorative schemes. These colors are Sun Tan, French Grey, Persian Red, Citrus Yellow, Pale Jade, India Ivory, Sky Blue and Shell Pink. All Crane colors possess a uniform quality and brilliance because they are fused into the smooth glaze of the fixtures and there is no possibility of fading.

## Crane equipment for your bathroom



The same high quality and styling that characterize Crane kitchen fixtures are available in bathroom fixtures. The Crane line includes a wide choice of matched groups and individual fixtures to meet every need and every budget. Crane also offers a complete selection of bathroom accessories.

Don't settle for anything less than a Crane *Preferred* kitchen—a modern, step-saving kitchen centered around a sparkling Crane *quality* sink. Here's why—

Crane sinks are of one-piece cast iron construction with glistening acid-resisting porcelain enameled finish that means lasting beauty. Corners are smoothly rounded, and there are no cracks or crevices to harbor dirt. To clean, you merely wipe with a damp cloth.

Recessed drainboards keep water from surging over the rim, and there is a convenient ledge for glasses or other kitchen equipment. A four-inch back protects the wall—permits a neater installation under low windows.

And the most beautiful cabinets you've ever seen—made of glistening enameled steel with special features and the very best of accessories.

Furthermore, you'll find the Crane Dealer has everything you need to make the kitchen a modern, efficient work center—ranges, garbage disposers, ventilating fans, water heaters and water treating equipment—even glistening white laundry trays for the combination kitchen-laundry room. His expert installation assures lasting service and satisfaction.

## Deluxe features are regular equipment

*Dial-ese* controls—one of the biggest convenience features of all Crane sinks. This exclusive Crane engineering advancement lets you turn faucets on and off with finger-tip pressure. But most important, because *Dial-ese* faucets operate so easily, wear and consequent dripping are reduced.

Handy Hose spray is another extra that really saves time. Has many uses in the preparation of food and in dishwashing. Just pull it out, press the thumb-action control, and there's water where you want it.

Basins of all Crane sinks are equipped with potentated *Receptol* wastes which have large cup strainers that are easily removed and emptied. A twist and the *Receptol* waste is back in position.



## Crane equipment for your heating system



Regardless of the type of heating preferred, or the fuel to be burned, the complete Crane heating line includes all equipment—boilers, furnaces, radiant baseboard panels, Compac radiators, convectors, oil and gas burners, stokers, controls, water specialties, pipe, valves and fittings.

# the *Kitchen Queen* kitchen

**KITCHEN QUEEN SINK 5-40-S**—Double-basin, double-drainboard sink made of finest acid-resisting porcelain enameled cast iron. The beveled fixture panel, 4-in. high back, depressed drainboards and two soap depressions combine to make this sink the last word in sink styling.

Chromium-plated *Temple* supply fitting has swinging spout and *Dial-ese* controls. Thumb-action spray with retractable rubber hose.

Each sink compartment is equipped with a *Receptol* waste with a removable cup strainer. Outlet accommodates electric garbage disposer, if desired.

The attractive *Kitchen Queen* cabinet is made of steel, bonderized for corrosion resistance, and has a lustrous white baked enameled finish. Handles and knobs are heavily chromium plated. Rubber bumpers at all points of contact protect cabinet finish and give quiet action. Recessed knee and toe space for comfort.


Smooth-gliding, double-faced drawers are sound insulated and supported on steel channels for sturdiness and smooth, quiet operation. Interlocking roller type slides hold drawers firmly shut. Drawers are easily removed for cleaning.

Easy-acting, double-faced doors are also sound insulated. Concealed toggle spring hinges hold doors in open or closed position.

Sink size: 72 x 25¼ in.

Basins: 18 x 16 x 8 in.

Cabinet size: 70¾ x 24¾ in. Height: 34¾ in. (sets sink 36 in. floor to rim).



## CABINET ACCESSORIES

- Removable cutting board in left-hand top drawer.
- Removable cutlery tray in right-hand top drawer.
- Wire utility basket on large left-hand door, under basins.
- Removable shelf in small compartment at left-hand side.
- Sliding towel rack in small compartment at right-hand side.

## CABINET ARRANGEMENT

- Two shallow roller drawers.
- Two deep roller drawers.
- One cupboard with roller tray on right-hand side.
- Large cupboard and utility space under basins.
- Two small compartments under basins.



# the *Sunnyday* kitchen



## CABINET ACCESSORIES

- Removable cutlery tray in right-hand top drawer.
- Removable cutting board in left-hand top drawer.
- Wire utility basket on left-hand door.

## CABINET ARRANGEMENT

- Two shallow roller drawers.
- Two deep roller drawers.
- One cupboard with roller tray on right-hand side.
- Large cupboard and utility space under basin.

**SUNNYDAY SINK 5-50-S**—Popular single-basin, double-drainboard sink of acid-resisting porcelain enameled cast iron. 4-in. high back, two soap depressions, beveled fixture panel. Drainboards are depressed to keep water from surging over the rim.

Chromium-plated Temple supply fitting has swinging spout and Dial-ese controls. Thumb-action spray with retractable rubber hose.

The Sunnyday sink comes equipped with a Receptol waste with the handy removable cup strainer. Outlet accommodates electric garbage disposer, if desired.

The efficiency planned Sunnyday cabinet is made of steel, bonderized for corrosion resistance, and has a lustrous white baked enameled finish. Handles and knobs are chromium plated. Rubber bumpers at all points of contact protect cabinet finish and allow quiet action. Recessed knee and toe space allows greater comfort while working.

Smooth-gliding, double-faced drawers are sound insulated and supported on steel channels for sturdiness. Interlocking roller-type slides hold drawers firmly shut. Drawers are easily removed for cleaning.

Easy-acting, double-faced doors are sound insulated with a rust-resistant material. Concealed toggle spring hinges hold doors in open or closed position.

Sink sizes: 54 x 25 $\frac{1}{4}$  in.      Basin: 20 x 18 x 8 in.  
60 x 25 $\frac{1}{4}$  in.      22 x 18 x 8 in.

Cabinet sizes: 52 $\frac{3}{4}$  x 24 $\frac{3}{4}$  in. Height: 34 $\frac{3}{4}$  in.  
58 $\frac{3}{4}$  x 24 $\frac{3}{4}$  in. (Sets sink 36 in. floor to rim.)



# the *Kitchen Pride* kitchen

**KITCHEN PRIDE SINK 5-44-S**—Compactly styled, finest acid-resisting porcelain enameled cast iron sink with two 8-in. deep basins. Features a 4-in. high back to protect the walls, beveled fixture panel and two soap depressions.

Chromium-plated *Temple* supply fitting has swinging spout and *Dial-ese* controls that turn with finger-tip pressure. Thumb-action spray with retractable rubber hose reaches every corner of the sink.


Each sink compartment is equipped with a *Receptol* waste with removable cup strainer. Outlet accommodates an electric garbage disposer, if desired.

The attractive and compact *Kitchen Pride* cabinet is made of steel, bonderized for corrosion resistance, and has a lustrous white baked enameled finish. Handles and knobs are chromium plated. Rubber bumpers at all points of contact protect the cabinet finish. Recessed knee and toe space across entire cabinet front for working comfort.

Easy-acting, double-faced doors are sound insulated. Concealed toggle spring hinges hold doors in open or closed position.

Like all Crane cabinets, welded construction, with ample bracing and extra heavy gussets at strategic points, assure strength and sturdiness.

Sink size: 38 x 25¼ in. Basins: 18 x 16 x 8 in.  
Cabinet size: 36¾ x 24¾ in. Height: 34¾ in.  
(Sets sink 36 in. floor to rim.)



## CABINET ACCESSORIES

- Removable shelf in small compartment at left-hand side.
- Sliding towel rack in small compartment at right-hand side.
- Wire utility basket on large left-hand door.

## CABINET ARRANGEMENT

- Large cupboard and utility space.
- Two small compartments.



# the *Homemaker* kitchen



## CABINET ACCESSORIES

- Removable cutlery in top drawer.
- Wire utility basket on left-hand door.

## CABINET ARRANGEMENT

- One shallow roller drawer.
- Two deep roller drawers.
- Large cupboard and utility space under basin.

**HOMEMAKER SINK 5-82-S**—Single-basin, single-drainboard beauty of a sink, made of finest acid-resisting porcelain enameled cast iron. Quality features include 4-in. high back, ledge for glasses, soap depression. The chromium plated *Embassy* supply fitting has a swinging spout and exclusive *Dial-ese* controls. There is also a thumb-action spray with retractable rubber hose and a *Receptol* waste with removable cup strainer. If desired, the *Homemaker* may be equipped with an electric garbage disposer. Specify *Homemaker 5-81-S* for left-hand drainboard model.

The *Homemaker* cabinet is made of steel, bonderized for corrosion resistance, and has a lustrous white baked enameled finish. Handles and knobs are chromium plated. Rubber bumpers at all points of contact protect the cabinet finish. Recessed knee and toe space for comfort.

Smooth-gliding, double-faced drawers are sound insulated. Interlocking roller type slides with stops hold drawers firmly shut. Drawers are easily removable for cleaning.

Easy-acting, double-faced doors are sound insulated with a material that is also rust-resistant. Concealed toggle spring hinges hold doors in open or closed position.

Sink size: 42 x 25¼ in.

Basin: 20 x 18 x 8 in.

Cabinet size: 40¾ x 24¾ in. Height: 34¾ in.

(Sets sink 36 in. floor to rim.)



# Crane *Sunnycrest Sink*

**SUNNYCREST SINK 5-100-S**—Finest acid-resisting porcelain enameled cast iron sink with 8-in. deep basin, two depressed drainboards and 4-in. high back. There is also a ledge for glasses and two handy soap depressions. The striking chromium-plated *Embassy* supply fitting has a swinging spout and exclusive Crane *Dial-ese* controls. A *Receptol* waste with removable cup strainer is also provided. Outlet accommodates electric garbage disposer, if desired.

The attractive *Sunnycrest* cabinet is made of steel, bonderized for corrosion resistance, and has a lustrous white baked enamel finish. Double-faced doors and drawers are sound insulated with a material that is also rust-resistant. Interlocking roller type slides with stops hold drawers firmly shut. Concealed toggle spring hinges hold doors in open or closed position. Rubber bumpers are installed at all points of contact. Recessed toe space.

Sink sizes: 54 x 22½ in.,  
60 x 22½ in.

Basin: 20 x 15 x 8 in.,  
22½ x 15 x 8 in.

Cabinet sizes: 52¾ x 22 in.,  
58¾ x 22 in.

Height: 34¾ in.  
(Sets sink 36 in. floor to rim.)



## CABINET ACCESSORIES

- Wire utility basket on left-hand door.

## CABINET ARRANGEMENT

- Two shallow roller drawers.
- Two deep roller drawers.
- One cupboard with shelf on right-hand side.
- Large cupboard and utility space under basin.

**STEWARDESS SINK 5-103-S**—Made of finest acid-resisting porcelain enameled cast iron with a single 8-in. deep basin, depressed drainboard and 4-in. high back. Features a convenient ledge for glasses and a handy soap depression. The chromium-plated *Embassy* supply fitting has a swinging spout and exclusive Crane *Dial-ese* controls that turn with finger-tip pressure. Basin equipped with *Receptol* waste with removable cup strainer. Outlet accommodates electric garbage disposer, if desired. Also available in right-hand drainboard model as *Stewardess* 5-106-S.

The modern *Stewardess* cabinet is made of steel, bonderized for corrosion resistance, and has a lustrous white baked enamel finish. Double-faced doors and drawers are sound insulated with a material that is also rust-resistant. Interlocking roller type slides with stops hold drawers firmly shut. Concealed toggle spring hinges hold doors in open or closed position. Rubber bumpers at all points of contact protect cabinet finish. Recessed toe space.

Sink size: 42 x 22½ in.

Basin: 20 x 15 x 8 in.

Cabinet size: 40¾ x 22 in.

Height: 34¾ in.  
(Sets sink 36 in. floor to rim).

## CABINET ACCESSORIES

- Wire utility basket on left-hand door.

## CABINET ARRANGEMENT

- One shallow roller drawer.
- Two deep roller drawers.
- Large cupboard and utility space under basin.




# *Stewardess Sink*



# *built-in sinks and counter-tops for*

If your plans call for a continuous counter-top kitchen arrangement, you can have a Crane sink and counter-top combination built to your specifications. Shown here is everything you need to make a counter-top kitchen of convenience and beauty.



Here is a fine example of the utility possible in a custom counter-top arrangement. In this attractive layout, the *All-American* double-basin sink is shown with an under-sink cabinet. Matching base cabinets flank the under-sink cabinet, and the entire grouping becomes a built-in unit with a continuous counter-top. The U-shaped grouping shown is only one of the attractive arrangements possible with a Crane built-in sink, matching cabinets and a custom counter-top.



**THE ALL-AMERICAN SINK 5-124-S**—The finest counter-top sink available. One-piece, finest acid-resisting porcelain enameled cast iron construction. Two 8-in. deep basins and 4-in. high back. Chromium-plated *Temple* trim with lever handle *Dial-ese* controls, swinging spout and retractable hose spray. Outlets accommodate electric garbage disposer, if desired.


Sink size: 38 x 22 in. Basins: 17 x 15½ x 8 in.

**THE SINK**—Crane offers a wide selection of flat rim sinks designed especially for installation in your choice of counter-top. These modern flat rim sinks are all Crane quality, made of finest materials with such exclusive features as *Dial-ese* controls and *Receptol* wastes. Available in single and double-basin models.

**THE COUNTER-TOPS**—Counter-tops are also available from Crane, custom built to your specifications whether straight, L-shaped or U-shaped, with or without back splash. The selection of color and material is complete. Choose linoleum, plastic, stainless steel, or maple.

**THE UNDER-SINK CABINET**—Under-sink cabinets used in conjunction with counter-tops are regulars from the Crane line. You need only choose the under-sink cabinet you desire. Double-basin sinks, of course, require a double-basin size cabinet.

**BASE CABINETS**—The modern base cabinets shown in these typical arrangements are designed especially to allow flexible arrangements. They may be arranged to create the effect and convenience you desire.



**5-251-S COMBINATION**—The attractive double-basin sink in this counter-top unit is the 5-131-S, made in one piece of finest acid-resisting porcelain enameled cast iron. Has chromium-plated *Embassy* trim with *Dial-ese* controls and handy *Receptol* wastes. The unit comes complete as shown with Crane-Line Kitchen Queen cabinet and Formica on wood core counter-top.

Size: 72 x 25¼ in. Basins: 14¼ x 15½ x 8 in. Back: 4 in.

## **Types of Counter-Tops**

**WOOD CORE**—Unless otherwise specified, counter-tops will be supplied with wood core. Plastic or linoleum covered. Semi-flush stainless steel trim.

**STAINLESS STEEL**—For those installations where a stainless steel counter-top is desired, Crane can supply lengths and patterns to suit.

**MAPLE CUTTING TOPS**—May be joined into a continuous top of either linoleum, Formica or Textolite if desired.

# continuous installations



**5-254-S COMBINATION**—Compactly styled with the 5-136-S single-basin sink. This quality sink is also one-piece construction, made of finest porcelain enameled cast iron. Has chromium-plated *Embassy* trim with *Dial-ese* controls and handy *Receptol* waste. Completing this modern combination is the Crane-Line *Homemaker* cabinet and a Formica on wood core counter-top. Available in left-hand drainboard model as 5-253-S.

Size: 42 x 25¼ in. Basin: 21½ x 15½ x 8 in. Back: 4 in.



**5-252-S COMBINATION**—Features the 5-146-S single-basin sink which is made of formed metal, porcelain enameled. Also has chromium-plated *Embassy* trim with *Dial-ese* controls and a handy *Receptol* waste. The attractive cabinet is the Crane-Line *Sunnyday*. The counter-top is Formica on wood core.


Sizes: 60 x 25¼ in. Basin: 21 x 15 x 8 in. Back: 4 in.  
54 x 25¼ in. 21 x 15 x 8 in. 4 in.

## Colors and Materials


**LINOLEUM**—Wide selection of colors to choose from including reds, greens, blues, yellow, black, terra cotta, tan and brown.

**TEXTOLITE**—Available in reds, blues, greys, greens, brown, slate, tan and fawn.

**FORMICA**—Choose from greys, blues, green, reds, tans, and yellow.





Typical counter-top for corridor kitchen arrangement



Typical counter-top for L-shaped kitchen arrangement

## CUSTOM COUNTER-TOPS

Your Crane Dealer can supply a counter-top to fit your kitchen exactly. These break-away illustrations show how the one-piece counter-top is made to fit on your choice of base cabinets. Notice that counter-tops are available in straight, L-shaped or U-shaped designs. Individual tops for base cabinets or sink cabinets are also made to your specifications.




Typical counter-top for U-shaped kitchen arrangement

# Crane-Line *matching wall and base cabinets*

Here is the answer to your kitchen storage problems—sparkling new Crane-Line cabinets to make any kitchen a model of efficiency and utility. They are functional in design and possess construction features not found in ordinary cabinets. Both wall and base models are made of highest quality steel, bonderized for corrosion resistance, and have a durable, sanitary and lustrous baked white enamel finish that is easy to keep clean and bright. Attractive, well-rounded edges minimize chipping of enamel. Note, too, the manner in which cabinets may be placed side by side without filler strips. This is possible because all doors open to 90°—the face of the door does not extend beyond the side of the cabinet. In fact, the many models and sizes of Crane Line wall and base cabinets permit you to arrange them any way you may desire.



Easy-acting, double-faced drawers and doors are sound insulated with a material that is also rust resistant. Rubber bumpers minimize sound. Toggle spring hinges hold doors in open or closed position.



White baked enameled steel shelves on all wall cabinets are adjustable—easily removed for cleaning. Holes are conveniently located at back for supporting screws.




All Crane-Line wall cabinets are provided with a convenient finger recess, eliminating handle hardware on the face of the door, simplifying cleaning.




Recessed back design is another important feature. End panels only contact the wall—minimize installation difficulties encountered in uneven wall surfaces.

## features of Crane-Line cabinets

Welded construction, with ample bracing and extra heavy gussets at strategic points, provides strength and sturdiness. Gussets are provided with holes for attachment of work tops.




Drawers are supported on formed steel channels with interlocking roller type slides with stops—keep drawers firmly closed. Non-metallic roller bearings and rubber bumpers for quietness.



Handles are of modern design and practical shape, and heavily chromium-plated for attractive appearance. Positioned for perfect line-up with under-sink cabinet.



Modern recessed toe base affords comfort while standing. Matches perfectly the design of Crane-Line under-sink cabinets. Smooth, rounded edges on doors and drawers.




# Crane-Line Cabinet

*sizes*

Crane-Line Wall and Base Cabinets are available in sizes to meet the requirements of any kitchen plan. Illustrated here is the complete line with dimensions listed. These overall dimensions will assist you in determining the best grouping for your kitchen.


Base cabinets do not regularly include work tops. Your choice of counter-top may be selected from the listing on previous page. They are available for the individual cabinet or any group of cabinets in your particular kitchen arrangement.

## wall cabinets




**5-576**  
Two Doors and One Shelf

WIDTH	21"	24"	30"	36"
DEPTH	13"	13"	13"	13"




**5-570-R**—Right-Hand Hinge  
**5-570-L**—Left-Hand Hinge  
Single Door and Two Shelves

WIDTH	15"	18"
DEPTH	13"	13"



**5-573**  
Two Doors and Two Shelves

WIDTH	21"	24"	27"	30"
DEPTH	13"	13"	13"	13"



**5-579-R** CORNER—Right-Hand Hinge  
**5-579-L** CORNER—Left-Hand Hinge  
Single Door and Two Shelves

WIDTH	23 1/2"
DEPTH	13"

## base cabinets

**5-560-R** CORNER—Right-Hand Corner (Illustrated)  
**5-560-L** CORNER—Left-Hand Corner  
One Shallow Drawer and Cupboard with Single Door Hinged at Center

WIDTH	40 3/4"
DEPTH	22"

**5-556**  
One Shallow Drawer and Two Deep Drawers

WIDTH	18"	18"	24"
DEPTH	22"	24 3/4"	24 3/4"

**5-550-R**—Right-Hand Hinge  
**5-550-L**—Left-Hand Hinge  
One Shallow Drawer and Cupboard with Single Door and Shelf






WIDTH	15"	15"	18"
DEPTH	22"	24 3/4"	24 3/4"

**5-553**  
One Shallow Drawer Cupboard with Two Doors and Shelf

WIDTH	21"	21"	24"
DEPTH	22"	24 3/4"	22"
W.	24"	27"	30"
D.	24 3/4"	24 3/4"	22"

**5-568 UTILITY**—Four Doors and Six Shelves  
**5-566 IMPLEMENT**—Four Doors, Two Shelves and Implement Hooks

WIDTH	21"
DEPTH	13"



*the easy way to plan with*

# Crane *Preferred* kitchens

Here's how to gain the step-saving convenience of a modern Crane cabinet kitchen with minimum effort—minimum expense. Choose a Crane *Preferred* Kitchen ensemble, planned especially for quick, easy installation in any kitchen without the need of extensive remodeling and other inconvenience.

There is probably an ensemble illustrated that will fit your kitchen to a "T." However, cabinets shown in these selected ensembles may be rearranged if desired, or you may choose other types and sizes to suit your individual requirements.



**ENSEMBLE A**—Wide and handsome with the Kitchen Queen double-basin double-drainboard sink and under-sink cabinet as the center. In addition, there are two wall cabinets and two base cabinets. Measures 10 feet overall. Truly a beauty, if space permits.



**ENSEMBLE H**—10 feet long and all utility. Ensemble includes All-American double-basin sink with Kitchen Queen under-sink cabinet, Dish-a-matic dishwasher unit and Waste-King Pulverator. A practical combination with ample counter-top and wall cabinets.




**ENSEMBLE C**—Double-basin Kitchen Pride sink and under-sink cabinet with a planned grouping of wall and base cabinets afford big kitchen utility in minimum space—93½ inches, to be exact.



**ENSEMBLE D**—For the corner plan, consider this ensemble which incorporates the compact Homemaker single-basin, single-drainboard sink and under-sink cabinet. The ensemble requires 86½ inches on the sink wall—83½ inches on the adjoining wall.

**ENSEMBLE E**—If space is the problem, Ensemble E with the Sunnycrest single-basin, double-drainboard sink and under-sink cabinet may be the solution. You can expand on this group, of course, if you like. As is, overall measurements are 75 inches with 54-inch sink—78 inches with 60-inch sink.



**ENSEMBLE F**—Another well planned ensemble for the corner layout. Features the budget-priced Stewardess single-basin, single-drainboard sink with under-sink cabinet that provides adequate storage and work area for an average sized home. Measures 89½ inches on the sink wall—41½ inches on adjoining wall.



**ENSEMBLE G**—Here the double-basin All-American sink with Kitchen Pride under-sink cabinet installed in a continuous counter-top. Planned storage space below and above completes this interesting ensemble. 88½ inches required on sink wall—41½ on adjoining wall.




# Electric Range

More than twenty-five arrangements are possible with the new Universal automatic electric Select-a-Range. Each unit is self-contained and may be installed individually or in any combination desired. Blends perfectly with Crane-Line base and wall cabinets. Start with an economy arrangement—add to it later. Note how the oven may be placed at the "convenience level" height to eliminate stooping and bending. It's a homemaker's dream—and easily financed because of its built-in design.



Oven Unit 20 in. wide x 25 1/8 in. front to back x 24 1/4 in. high.  
Cooking Unit 20 in. wide x 25 1/8 in. front to back x 9 in. high.  
Drawer Unit 20 in. wide x 25 in. front to back x 7 3/8 in. high




RA9403 Storage Drawer Unit has drawers mounted on brass runners and fitted with rubber bumpers for quiet operation. RA9405 Storage Drawer Unit is similar in construction but has steel sub-base with recessed toe space.



RA9402 Platform Surface Cooking Unit has four Super-heat Monotube units. Heating plates swivel-mounted, easily cleaned. Heat control has seven positions from slow simmer to hard boil. Removable drip tray. Counter plate also available.




RA9401 Oven has automatic push-button pre-heat and automatic timer. Smokeless broiler equipped with pan. Mini-Minder times any kitchen task. Temperature control assures balanced oven heat.



Install Individually



For Larger Homes




Economy Arrangement

# Dishwasher


Now you can choose a famous *Apex* dishwasher to fit your space—and your budget. Each of the models shown here has the famous built-in water heater and will automatically—and quietly—wash, rinse and dry all dishes, glassware and silverware for a family of five or six at one time.




Model 970—Designed as a free-standing unit to be installed separately or in conjunction with Crane-Line base cabinets. Beautiful white baked enameled steel cabinet with acid-resisting porcelain enameled steel lid. Removable front panel. Also available with 14-inch diameter, heat-proof "look-in" lid and illuminated interior as Model 970-1. Width 24 in., depth 25 in., floor to top of rim 36 in.



Model 890—Roll-a-Way model requires no special installation. With one setting of the dial, full service for a family of five is automatically washed, rinsed twice and dried—all in 30 minutes. Cabinet is all-steel with white baked enamel finish. Cover and tub are white laminated Fiberglas. Heavy-duty pump. Rolls free on rubber casters. Uses 3 1/2 gallons of average temperature hot water. Width 24 in., depth 17 in., floor to top 36 in.



Model 990—Drop-in model for installation in continuous work surfaces in conjunction with Crane-Line base cabinets. Easily installed by means of polished aluminum mounting ring and gasket to provide a water-tight seal. Porcelain enameled steel lid is only part visible when closed. Timer control panel mounts on wall, back splash or on front of cabinet of your choice.



# garbage *disposers*

**IN-SINK-ERATOR**—All food wastes are quickly carried away by In-Sink-Erator's automatic whirlpool. Patented reversing action doubles life of shredding elements—also adds a unique self-cleansing feature. Safety baffle shields opening, preventing back-splash and affording quieter operation. Easily installed in any Crane sink.

**WASTE KING PULVERATOR**—Operates in three simple steps. Turn on the water—Flip the switch—Scrape all food wastes into the drain opening. The continuous feed principle of the Waste King allows all food waste to go into the unit at the same time. There is no sorting of waste—no stopping and starting. Precision made.



Automatic garbage disposers fit neatly out of the way in cabinet under sink basin.

# Crane *Laundrette*


Protect clothes with this new, sparkling white laundry tray. There are no sharp edges or rough surfaces to snag those silks and nylons—that's because it's made of Duraclay, the exclusive Crane vitreous glazed earthenware material. The *Laundrette* will also bring new efficiency and brightness to your laundry room. It has two large capacity tubs, a molded-in washboard, a handy shelf and many other outstanding features, including *Dial-ese* controls and swing spout. The 6-111 *Laundrette* is made in 36 and 42 in. sizes.



Or you may prefer the 22 in. 6-115 single compartment model, ideal for use with an automatic washer.

## VENTILATING FANS

**CR-20 BUILT-IN TYPE**—Quickly removes grease, steam, heat and objectionable odors given off from cooking and dishwashing. Also ideal for bathroom, laundry and game room. Weather-tight door automatically opens when fan is actuated by pull chain. Also available in wall switch models as CR-30. Portable models also available.



# Crane-Line *water heaters*



**CRANE-LINE SUPERIOR**  
Finest gas-fired water heater made. Available in 30 and 45-gallon sizes.



**CRANE-LINE KEYSTONE**  
An excellent gas-fired water heater for the average home. 20, 30 and 40-gallon sizes.



**CRANE-LINE CHAMPION**  
Low initial cost—low up-keep with this quality gas-fired heater. 20, 30 and 40-gallon sizes.




**CRANE-LINE SELECTRIC**  
Efficient electric water heater. Made in 30, 40, 52, 66, 80 and 100-gallon sizes.

Enjoy around-the-clock hot water service with any of these quality Crane-Line water heaters. They are modern in design, completely safe and offer many exclusive features that you will appreciate. Your Crane Dealer will gladly explain the advantages of each heater and help you choose the proper model for your particular requirement.

## GAS RANGES

The Odin Beautyrange is a most attractive gas range that will be right at home in a new Crane kitchen. Divided one-piece china-white porcelain top. Seamless one-piece oven with bright chrome-finished linings. Swing-out Hi Broiler and Barbequer. Many other exclusive features to help lighten cooking tasks. Available for use with natural, manufactured or bottled gas. Electric models also available.




## *water treating equipment*



**CRANE-LINE SOFTENALL**—Attractive, highly efficient water conditioner softens the hardest of fresh waters and also removes light sediment, iron and manganese simultaneously with the softening process. Tanks are made of heavy grade steel, electrically welded. Salt tank capacities from 90 to 220 pounds.


**CRANE-LINE FILTER, PURIFIER AND NEUTRALIZER** for treating waters with high iron content, odors, tastes and acids. Filters sediments, iron rust, turbidity. Removes undesirable tastes, odors and color from water, especially those caused by organic matter or decaying vegetation. Neutralizes acid waters to the alkaline side. Galvanized steel tank. A size for every home.

## cabinet accessories



**5-289**—These corner shelves are designed to finish off the end of wall cabinets and provide a handy place for clock, calendar or small objects. Ideal for small plants or vines. For semi-circular shelves, specify 5-286.

**5-280**—Used at the end of a breakfast bar or of a row of base cabinets, these shelves add to the appearance of a kitchen and provide a convenient place to keep appliances.



**5-610**—Keep towels right at your finger tips. This towel bar fits in under-sink or base cabinets and slides out for added convenience.




**5-614**—Cup hook racks are easily attached to the under side of any shelf. Sizes to accommodate 6 or 8 cups.




## molding and filler strips



**5-624**—This convenient flour dispenser may be attached to the shelf in any wall cabinet. Dispenser slides out for easy accessibility.



**5-618**—Metal bread box for large drawer in under-sink and base cabinets. Handy sliding top for easy access.




**5-621**—Three-piece canister set for flour, sugar, meal, etc. Each bin has own lid. Fits in large drawers, in under-sink and base cabinets.



**5-642**—Wire condiment step shelf rack for orderly storage of spices, small boxes, etc. Every item is visible and easily accessible.



**5-633**—Metal rack for convenient storage of pans and lids. May be attached to inside of cabinet doors.




**5-630**—Handy basket fastens to inside of cabinet doors. May be used for soap, soap powders, brushes, etc. Also has bar for dish cloths.



**5-639**—Condiment rack that attaches to inside of cabinet doors. Conveniently holds small boxes and containers; 9 inches wide.



**5-627**—Here's a place to store favorite recipe cards. A handy rack that fastens inside any cabinet door.



**5-636**—Another handy accessory for storing pans and lids. Four compartments hold pans and lids 6 to 11 inches in diameter.

**FILLER PIECES** are used with wall cabinets and base cabinets. They are used only in those rare instances where Crane-Line cabinet groupings do not exactly fit the available space. Made of white baked enameled steel. Types for every need.

**MOLDING STRIPS** are used to make the joint between sink rim and counter-top. Available in chromium plate and stainless steel.

# CRANE CO.

CRANE CO. • 836 S. MICHIGAN AVENUE • CHICAGO 5, ILLINOIS